



ಪಿಲಿಕುಲಾ ಅಭಿವೃದ್ಧಿ ಪ್ರಾಧಿಕಾರ

PILIKULA DEVELOPMENT AUTHORITY

NO. PND .CR.195/PBP/2021-22

DATE :31/12/2021

04/01/2022

QUOTATION NOTIFICATION

Rate quotations are invited by the Commissioner, Pilikula Development Authority, Mangaluru for the work of Providing chain link partition inside spotted deer enclosure in Pilikula Biological Park at Pilikula, Mangaluru.

| SI NO | PARTICULARS | QTY | UNIT | RATE |
|-------|--|------|------|------|
| 1 | KSRB 2-2: Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits or in trenches , stacking the excavated soil clear from edges of excavation with lead upto 50m. including breaking of clods complete as per specifications. | | | |
| | in hard soil No. KBS 2.1(b)/2.3.5 | 5.91 | M3 | |
| 2 | KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. specification No.KBS 4.1,4.2 | 3.33 | M3 | |
| 3 | KSRB 5.1: Providing and constructing granite/ trap/ basalt rubble stone masonry in foundation with cement mortar (uncoursed), bond stones at 2m. Apart in each course including cost of materials, labour, curing complete as per specifications. KBS 1.12 | 2.02 | M3 | |

| | | | | |
|---|---|-------|-----|--|
| 4 | Providing labour towards preparing available wooden poles of minimum 100mm dia and shifting to the site and placing in excavated trenches at 1.80m c/c, including stretching of 3" x 3" expanded metal of gauge 10 and binding it with GI wires and U nails at every 0.90m intervals vertically | 90.00 | sqm | |
| 5 | KSRB 15-18.1: Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler for varnish including cost of materials, labour, complete as per specifications. | 90.00 | sqm | |
| 6 | KSRB 15-18.2: Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. | 90.00 | sqm | |

Conditions:

1. The last date for the receipt of quotation is 10/01/2022
2. The rate quoted shall be inclusive of all tax
3. The payment will be made after certification by the Project Engineer Pilikula Development Authority.
4. The under signed reserves the right to accept or reject the quotations without assigning any reason thereof.


Commissioner


ಆಡಳಿತ ಕಛೇರಿ: ಮೂಡುಶೆಡ್ಡೆ, ಮಂಗಳೂರು-575028, ದೂರವಾಣಿ: 0824-2263565, ಇ-ಮೇಲ್: pilikula96@gmail.com, ವೆಬ್‌ಸೈಟ್:

www.pilikula.com

Administrative Office: Moodushedde, Mangaluru-575028, Ph: 0824-2263565, e-mail:pilikula96@gmail.com, website:

www.pilikula.com